



INVITATION TO BID

The Iligan City Government Bids and Awards Committee (BAC), through **General Fund / SB No. 1 CY 2024**, intend to apply the sum of **P 1,932,247.35** being the Approved Budget for the Contract (ABC) to payments under the Contract for **STAGE, STALLS AND COMFORT ROOMS AT ESPLANADE (CONSTRUCTION OF COMFORT ROOMS AT ESPLANADE), BRGY. SANTIAGO, ILIGAN CITY** with Project No. **CB(B)-24-108 (CEO-INFRA)**. Bids received in excess of the ABC shall be automatically rejected at bid opening.

The Iligan City Government Bids and Awards Committee now invites for the supply and delivery of items below-stated:

PARTICULARS	APPROVED BUDGET FOR THE CONTRACT (ABC)	REQUIRED BID SECURITY
<p>Stage, Stalls and Comfort Rooms at Esplanade (Construction of Comfort Rooms at Esplanade), Brgy. Santiago, Iligan City</p> <p>1.) GENERAL REQUIREMENTS •Permits and Clearance •Installation of Project Billboard- 2 Sets •Occupational Safety and Health Program •Mobilization and Demobilization</p> <p>2.) EARTHWORKS •Excavation works for footings •100 mm thk. Gravel base for footings</p> <p>3.) STEEL REINFORCEMENTS •Installation of 20mm Ø DSB for columns (C1) and Beams •Installation of 16mm Ø DSB for footings (F1) and Beam Const. •Installation of 10mm Ø DSB stirrups for tiebeams and lateral ties •Installation of 12mm Ø DSB for floorslab matting and pump assembly</p> <p>4.) PLUMBING WORKS •Installation of soil pipeline using 4" Ø PVC pipes S1000 •Installation of waste pipeline using 2" Ø PVC pipes S1000 •Installation of 2000L Portable Septic Tank •Installation of coldwater line using 3/4" and 1/2" G.I pipes S40 •Installation of 2000L Vertical Water Tank on a fabricated platform</p> <p>5.) CONCRETE WORKS, FORMWORKS AND SCAFFOLDING •Installation of formworks and falseworks for columns beams and tiebeams •Concrete pouring for footings ,columns , plinth beams and beams •Installation of 100 mm thk. Slab flooring on a 1.0mm Thk. Steel Deck •Installation of Reinforced Concrete Ramps •Removal of formworks and falseworks •Concrete pouring for pump platform and Column- Footing</p> <p>6.) GROUTED RIPRAP •Installation of Class A Grouted Riprap H = 3.264 m; L = 15.45 m</p> <p>I. PERMIT & CLEARANCES (Q = 1.00 lumpsum) Includes Fire, Brgy. Clearance for Construction Fee, Professional Fee, White Print (A-3)-6 sets of Plans</p> <p>II. CONSTRUCTION SAFETY AND HEALTH PROGRAM (Q = 1.00 lumpsum) Includes Safety Shoes, Safety Helmet, Safety Gloves, Specialized PPE, First Aide Kit & Medicines.</p> <p>III. PROJECT BILLBOARD (Q = 2.00 set/s) Includes 4' x 8' Tarpaulin Print Billboard, 8' x 8' Tarpaulin Print Billboard, 2"x 2"x 8' Coco Lumber, 2"x 3"x 10' Coco Lumber, 2"x 3"x 14' Coco Lumber, Assorted sizes C.W Nails.</p> <p>IV. MOBILIZATION & DEMOBILIZATION (Q = 1.00 lot)</p> <p>V. EARTHWORKS (Q = 118.29 cu.m.) Includes Volume to be Excavated (V = 64.2938), Volume to be Backfilled (V = 49.6025), Gravel Bedding 1-1/2" Ø (V = 3.88125) (+15% shrinkage).</p> <p>VI. STEEL REINFORCEMENTS (Q = 4,557.94 kgs.) Includes 20mm dia. X 6m DSB, 16mm dia. X 6m DSB, 12mm dia. X 6m DSB, 10 mm dia. X 6m DSB, 4" Cutting Disc, #16 G.I Tie Wire.</p> <p>VII. PLUMBING WORKS (Q = 1.00 lot) Includes 4" dia. x 10' PVC Pipe S-1000; 4" dia. PVC Sanitary Wye, S-1000; 4"x2" dia. PVC Sanitary Tee , S-1000; 4" dia. PVC Elbow, 1/8 bend (45 deg.); 4" dia. PVC Clean Out w/Adapter & Plug; 4" dia. PVC Elbow, 1/4 bend (90 deg.); 4" x 2" dia. PVC Sanitary Wye; 2" dia. x 10' PVC Pipe S-1000; 2" dia. PVC P-Trap; 2" dia. PVC Wye; 2" dia. PVC Elbow, 1/8 bend (45 deg.); 2" dia. PVC Elbow, 1/4 bend (90 deg.); 3/4" diam. x 10'G.I. Pipe Water Supply Line; 3/4" X 1/2" diam. G.I. Reducer Tee; 3/4" diam. G.I. Elbow, 1/4 bend (90 deg.); 3/4"x 1/2" diam. G.I. Reducer Elbow, 1/4 bend (90 deg.); 1/2" diam. x 10'G.I. Pipe Water Supply Line (Sched. 40); 1/2" diam. G.I. Threaded Pipe Elbow, 90 deg.; 1/2" dia.G.I. Threaded Pipe Tee; 1/2" diam. Angle Valve; Teflon Tape, 3/4" x 10m; 2000L Portable Septic Tank; 2000 L Water Tank w/ Metal Platform (2 Cu.m).</p> <p>VIII. CONCRETE WORKS, FORMWORKS AND SCAFFOLDINGS (Q = 35.53 cu.m.) Includes Portland Cement (Type 1), Washed Sand, Washed Gravel, 4' x 8' x 1/4" thk. Marine Plywood, Assorted Sized Coco Lumber (2" x 2" x 10' & 2" x 3" x 10')-300 PCS, Assorted sized C.W Nails, Steel Deck (1.0mm) (to order cutlist)</p>	<p>P 1,932,247.35</p>	<p>2% of the ABC if Cash, Manager's Check; Bank Draft/Guarantee, Irrevocable letter of credit confirmed or authenticated by a Universal or Commercial Bank; and 5% of the ABC if Surety Bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security</p>

IX. GROUTED RIPRAP (Q = 29.40 cu.m.)

Includes Portland Cement (Type 1), Washed Sand, Washed Gravel Fill, Weep Holes (2" PVC, S 1000), Filter Cloth, Boulders (15-25kg).

Delivery period is within ONE HUNDRED NINE (109) calendar days from receipt of Notice to Proceed. Bidders should have completed, within three (3) years from the date of submission and receipt of bids, a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instruction to Bidders.

Bidding will be conducted through open competitive bidding procedures using a non-discretionary "pass/fail" criterion as specified in the Implementing Rules and Regulations (IRR) of Republic Act (RA) 9184, otherwise known as the "Government Procurement Reform Act".

Bidding is restricted to Filipino citizens/sole proprietorships, partnerships, or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino Citizens, pursuant to RA 5183 and subject to Commonwealth Act 138.

Interested bidders may obtain further information from Iligan City government and inspect the Bidding Documents during office hours from 8:00 a.m. – 12:00 p.m. and 1:00 p.m. – 5:00 p.m. at the Office of the Bids and Awards Committee, 2nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City.

The complete schedule of activities is listed, as follows:

<i>Activities</i>	<i>Schedule</i>
1. Issuance of Bid Documents	October 8 –29, 2024 – 8:00 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City
2. Pre-bid Conference	October 15, 2024 – 9:30 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City
3. Submission of Bids	October 29, 2024 – 9:30 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City
4. Opening of Bids	October 29, 2024 – 9:30 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City

A complete set of Bidding Documents will be available to prospective bidders upon payment of a non-refundable amount of P 5,000.00 to the Iligan City Government Cashier, at the **BAC Office, 2nd Floor, City Hall Main Building, Buhanginan Hills, Pala-o, Iligan City.**

The Iligan City Government reserves the right to accept or reject any bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders.

Furthermore, the City Government of Iligan assumes no responsibility whatsoever to compensate or indemnify bidders for any expense or loss incurred in the preparation and submission of the eligibility statements and bids.

Approved by:


DARWIN O. MANUBAG, PhD.

BAC Chairman

Date of Advertisement Posting: October 8, 2024

Place of Posting/Advertisement: City Hall/IBJT Bulletin Boards, Iligan Official Website, Phil-GEPS

ITB No. 24-108 (CEO-INFRA)