



REPUBLIC OF THE PHILIPPINES
City of Iligan

BIDS AND AWARDS COMMITTEE

Website : www.iligan.gov.ph Email : bac@iligan.gov.ph Telefax : 063 2253034

INVITATION TO BID Negotiated Procurement – Two Failed Biddings (Sec. 53.1)

The Iligan City Government Bids and Awards Committee (BAC), through Gen Fund-20% / Dev. Fund, intend to apply the sum of P 5,140,105.76 being the Approved Budget for the Contract (ABC) to payments under the Contract for **CONSTRUCTION OF STEEL HANGING BRIDGE ACROSS BAYUG RIVER, PANOROGANAN, BRGY. ROGONGON, ILIGAN CITY** with Project No. CB(B)-24-089 (CEO-INFRA) - Two Failed Biddings. Bids received in excess of the ABC shall be automatically rejected at bid opening.

The Iligan City Government Bids and Awards Committee now invites for the supply and delivery of items below-stated:

PARTICULARS	APPROVED BUDGET FOR THE CONTRACT (ABC)	REQUIRED BID SECURITY
<p>Construction of Steel Hanging Bridge Across Bayug River, Panoroganan, Brgy. Rogongon, Iligan City</p> <p>Scope of Work: General Requirements Installation of Project Billboard Occupational Safety and Health Program Mobilization/Demobilization Removal/Demolish existing structure</p> <p>Earth Works Excavation works for dead-man A, dead- man B, foundation of column-footing and foundation of grouted riprap Backfilling of common soil must be compacted layer by layer</p> <p>Bridge Construction Reinforcing steel must be grade 40 with a tensile stress of at least 280 Mpa Cutting/bending, Installation/fastening of 12mm ø deformed steel bar for dead-man A and dead-man B and a use of #16 tie wire Cutting/bending, Installation/fastening of 20mm ø deformed steel bar for column-footing with 10mmø lateral ties for column Approached concrete slabs are reinforced with 10mm ø and 12mm ø deformed steel bar spaced at 400mm O.C, B.W. Pouring of Deadman A and Deadman B with 50mm plain round anchor bar in deadman A and 25mm plain round anchor bar in deadman B with 4000 psi concrete mix as indicated on approved plan Supply of 1240 ln.m. 12mm ø wire rope for messenger cable support and stabilizer Fabrication/Installation of 20mm thk steel cap, 20mm thk steel bracket, 150x200x10mm thk wide flange beam and roller with 6mm thk pin lock Use 25mm and 38mm G.I Pipe for ramp railing post and handrail as indicated on approved plan Use 16mm uPVC Pipe Cable Casing (Inserted to column) as indicated on approved plan</p> <p>Grouted Riprap Works Grouted riprap work is for ramps, abutments and slope protection with 4"ø weep holes Use stone ranging from 15kg to 25kg with at least 50% of the stones weighing more than 20kg Mortar for grouted riprap shall consist of sand, cement and water conforming the requirements given under Item 405 All walls of the abutments shall be provided with weepholes</p> <p>Painting Works Painting of columns, beams and steel structures All surfaces must be properly clean before repainting (1 coat primer, 2 coats final)</p> <p>I. GENERAL REQUIREMENTS A. PROJECT BILLBOARD (Q = 1.00 lot) Includes 4' x 8' TARPAULIN, 8' x 8' TARPAULIN, 2"x3"x 14" Coco Lumber, 2"x3"x10" Coco Lumber, 2"x2"x8" Coco Lumber, Assorted Sizes C.W. Nails. B. OCCUPATIONAL SAFETY AND HEALTH PROGRAM (Q = 1.00 lot) Includes Safety Shoes, Safety Helmet, Safety Gloves, Specialized PPE. C. MOBILIZATION / DEMOBILIZATION (Q = 1.00 lot)</p> <p>II. EARTHWORKS A. REMOVAL OF ACTUAL STRUCTURES (Q = 1.00 lot) B. STRUCTURAL EXCAVATION (COMMON SOIL) (Q = 103.22 m3)</p> <p>III. BRIDGE CONSTRUCTION A. REINFORCING STEEL BARS (Q = 4,416.00 kg.)</p>	<p>P 5,140,105.76</p>	<p>2% of the ABC if Cash, Manager's Check; Bank Draft/Guarantee, Irrevocable letter of credit confirmed or authenticated by a Universal or Commercial Bank; and 5% of the ABC if Surety Bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security</p>

<p>Includes Reinforcing Steel Bar, Grade 40; 25mm plain bar 4 pcs Grade 40; 50mm plain bar 4-pcs Grade 40; No. 16 G.I.Tie wire; Hauling Cost of Materials.</p> <p>B. STRUCTURAL CONCRETE CLASS A (MINOR STRUCTURES) (Q = 69.61 m3)</p> <p>Includes Portland Cement, Washed Sand, Gravel, Coco Lumber, Ordinary Plywood 1/2" thk., Assorted Sizes C.W. Nails, Skimcoat, Primer, Putty, Topcoat, Hauling Cost of Materials.</p> <p>IV. FINISHING</p> <p>A. STRUCTURAL STEEL AND WIRE CABLES (Q = 1.00 lot)</p> <p>Includes 12mm Messenger Wire cable, 150 x 200 x 10mm Thk. Wide Flange x 6m, 50mm Rigid Plain Round Bar Shafting, 100mm G.I Pipe S40, Steel Plate 20mm Thk., 38mm G.I Pipe S40 x 6m, 25mm G.I Pipe S40 x 6m, 10mm x 100mm Long Expansion Bolt, 100mm Base Plate, 16mm upvc pipe cable casting, Paint Roller 7" w/ Paint Tray, Epoxy Primer, Welding Rod, Cutting Disk, Grinding Disk, Hauling Cost of Materials.</p> <p>B. METAL STRUCTURE ACCESSORIES (Q = 1.00 lot)</p> <p>Includes Roller (Stainless), 16mm Bolt w/ 2 Nuts, Hauling Cost of Materials.</p> <p>V. SLOPE PROTECTION WORKS</p> <p>A. GROUTED RIPRAP (Q = 215.30 m3)</p> <p>Includes Portland Cement, Washed Sand, Boulders, 2" dia. PVC Pipe 10' (S-1000), Hauling Cost of Materials.</p>	
--	--

Delivery period is within ONE HUNDRED TWENTY (120) calendar days from receipt of Notice to Proceed. Bidders should have completed, within five (5) years from the date of submission and receipt of bids, a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instruction to Bidders.

Bidding will be conducted through open competitive bidding procedures using a non-discretionary "pass/fail" criterion as specified in the Implementing Rules and Regulations (IRR) of Republic Act (RA) 9184, otherwise known as the "Government Procurement Reform Act".

Bidding is restricted to Filipino citizens/sole proprietorships, partnerships, or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino Citizens, pursuant to RA 5183 and subject to Commonwealth Act 138.

Interested bidders may obtain further information from Iligan City government and inspect the Bidding Documents during office hours from 8:00 a.m. – 12:00 p.m. and 1:00 p.m. – 5:00 p.m. at the Office of the Bids and Awards Committee, Room 205, Left Wing, 2nd Floor, SP Bldg., Buhanginan Hills, Palao, Iligan City.


The complete schedule of activities is listed, as follows:

Activities	Schedule
1. Issuance of Bid Documents	October 22, 2024 – October 29, 2024 – 8:00 a.m. at BAC Office, Room 205, Left Wing, 2 nd Floor, SP Bldg., Buhanginan Hills, Palao, Iligan City
2. Submission of Bids	October 29, 2024 – 9:30 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City
3. Opening of Bids	October 29, 2024 – 9:30 a.m. at Casimero P. Cabigon Hall, 2 nd Floor City Hall Main Bldg., Buhanginan Hills, Pala-o, Iligan City

A complete set of Bidding Documents will be available to prospective bidders upon payment of a non-refundable amount of P 10,000.00 to the Iligan City Government Cashier, at the BAC Office, Room 205, Left Wing, 2nd Floor, SP Bldg., Buhanginan Hills, Palao, Iligan City.

The Iligan City Government reserves the right to accept or reject any bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders.

Furthermore, the City Government of Iligan assumes no responsibility whatsoever to compensate or indemnify bidders for any expense or loss incurred in the preparation and submission of the eligibility statements and bids.

Approved by: 

DARWIN MANUBAG, PH.D.
BAC Chairman

Date of Advertisement/Posting: October 22, 2024

Place of Posting/Advertisement: City Hall/IBJT Bulletin Boards, Iligan Official Website, Phil-GEPS

ITB No. 24-089 (CEO-INFRA)